

TILT-UP CONCRETE STRUCTURES

Reported by ACI Committee 551

Donald W. Musser
Chairman

Robert E. Truitt
Secretary

John Braga
Muriel Burns
Peter D. Courtois*
Mark E. Deardorff
George H. Ellinwood
Robert P. Foley
David W. Fowler
Dennis W. Graber
Judith Hardin
Harvey H. Haynes

Robert E. Haynes
Sam Hodges
Richard C. Hodson
David L. Kelly
Allan R. Kenney
Harry B. Lancelot, III
William E. Magee
Murray M. Parker
Alfred D. Perez, Jr.
James A. Rossberg

David M. Schierloh
Ben L. Schmid
William M. Simpson
Joseph Steinbicker
Don Thrailkill
Itzhak Tepper
Robert W. Theisen, Jr.
Joseph Varon
Gerry Weiler

* Served as initial committee chairman during formative stage of this report.

Tilt-up concrete construction is commonly used in low-rise building construction. This report discusses many of the items that should be considered in planning, designing, and constructing a quality tilt-up project. Major topics discussed include design, construction planning, construction, erection, and finishes.

Keywords: Analysis; box type system; composite construction; connections; cranes (hoists); diaphragms (concrete); earthquake resistant structures; erection; finishes; inserts; lifting hardware; load bearing walls; moments; parting agents; panels; rigging; roofing; sandwich structures; stability; strongback; structural design; tilt up construction.

CONTENTS

Chapter 1-Introduction, pg. 551R-2

- 1.1-Introduction
- 1.2-Definition
- 1.3-History
- 1.4-Advantages
- 1.5-Disadvantages
- 1.6-Scope of report

Chapter 2-Design, pg. 551R-4

- 2.1-General
- 2.2-Analysis
- 2.3-Loads
- 2.4-Design bending moment

- 2.5-Bending stiffness
- 2.6-Examples
- 2.7-Special design considerations
- 2.8-Building stiffness
- 2.9-Tolerances
- 2.10-Connections
- 2.11-Sandwich panels
- 2.12-Lifting analysis
- 2.13-Temporary bracing
- 2.14-Architectural/engineering documents
- 2.15-Reinforcement
- 2.16-Architectural considerations

Chapter 3-Construction planning, pg. 551R-31

- 3.1-Introduction
- 3.2-Site access and jobsite conditions
- 3.3-Coordination
- 3.4-Sequence of construction
- 3.5-Work platform
- 3.6-Curing compounds and bondbreakers
- 3.7-Lifting accessories
- 3.8-Shop drawings
- 3.9-Panel casting locations
- 3.10-Erection subcontractor
- 3.11-Final closure panel

Chapter 4-Construction, pg. 551R-34

ACI Committee Reports, Guides, Standard Practices, and Commentaries are intended for guidance in designing, planning, executing, or inspecting construction and in preparing specifications. References to these documents shall not be made in the Project Documents. If items found in these documents are desired to be a part of the Project Documents, they should be phrased in mandatory language and incorporated into the Project Documents.

ACI 551R-92 became effective February 1992.

Copyright © 1992, American Concrete Institute.

All rights reserved, including rights of reproduction and use in any form or by any means, including the making of copies by any photo process, or by any electronic or mechanical device, printed, written, or oral, or recording for sound or visual reproduction for use in any knowledge or retrieval system or device, unless permission in writing is obtained from the copyright proprietors.

- 4.1-Introduction
- 4.2-Site, subgrade, and slab
- 4.3-Construction practices and workmanship
- 4.4-Shop drawings
- 4.5-Materials and equipment
- 4.6-Supervision
- 4.7-Casting
- 4.8-Strip and clean panels
- 4.9-Seating on foundations
- 4.10-Backfill
- 4.11-Wall panel joints
- 4.12-Safety
- 4.13-Construction checklist

Chapter 5-Erection, pg. 551R-36

- 5.1-General
 - 5.1.1-Prior to construction
 - 5.3-Prior to erection day
 - 5.4-Safety meeting
 - 5.5-During lift
 - 5.6-Plumbing panels
 - 5.7-Bracing
 - 5.8-Closure panel

Chapter 6-Finishes, pg. 551R-39

- 6.1-Introduction
- 6.2-Finish face up
- 6.3-Finish face down
- 6.4-Concrete materials
- 6.5-Method and types of finish
- 6.6-Cleaning
- 6.7-Coatings
- 6.8-Cracking

Chapter 7-References, pg. 551R-44

- 7.1-Specified and/or recommended references
- 7.2-Cited references

Appendix A-Notation, pg. 551R-45

Appendix B-Construction checklist for wall panels, pg. 551R-45

Metric Conversions, pg. 551R-46

CHAPTER I-INTRODUCTION

1.1-Introduction

The technique of site-casting concrete wall panels on a horizontal surface and then lifting or “tilting” them into place is referred to as tilt-up construction. Tilt-up construction uses less forming material than cast-in-place concrete construction and minimizes heavy equipment usage, which results in savings in time, equipment, and manpower. This efficient and cost effective method of construction has been used in the United States since the early 1900’s. Tilt-up has

other countries around the world. The American Concrete Institute, recognizing the increasing interest in this type of construction, formed ACI Committee 551 in 1980. The Committee’s mission is to “study and report on the design and construction of tilt-up structures.”

This report is in conflict with ACI 318 in three areas. The first conflict is found in [section 2.7.5](#) and deals with the distribution of concentrated loads. The second conflict is found in [section 2.10.5](#), which discusses typical connection details between the panel, foundation, and slab-on-grade. The third conflict concerns the amount of shrinkage and temperature reinforcement required in a tilt-up panel and is found in [section 2.15.5](#). At the time this report was prepared, these three conflicts were being discussed with Committee 318 in an effort to eliminate them.

1.2-Definition

The definition for precast concrete found in ACI 116R is “concrete cast elsewhere than its final position,” and includes tilt-up concrete. A more specific definition of tilt-up construction is “a construction technique of casting concrete elements in a horizontal position at the jobsite and then tilting and lifting the panels to their final position in a structure.”

1.3-History

In 1909, Aiken¹ described an innovative method of casting panels on tilting tables and then lifting them into place by means of specially designed mechanical jacks. This technique was used for constructing target abutments, barracks, ammunition and gun houses, a mess hall, factory buildings, and churches (see Figs. 1.1 - 1.4).

In the mid-1950s, Collins²⁻⁴ wrote three volumes devoted to the entire process of tilt-up. These publications were *Design of Tilt-Up Buildings*,² *Manual of Tilt-Up Construction*,³ and *Building with Tilt-Up*.⁴ During this same time period, tilt-up concrete construction began to gain nationwide acceptance as techniques were refined. California led the way and Sun Belt states were quick to follow. Since that time, tilt-up buildings have been constructed in every state in the United States, and in other countries around the world.






Fig. 1.2-Wall raising jack

1.4-Advantages

There are many advantages in tilt-up construction for low and even mid-rise buildings, including industrial plants, warehouses, office buildings, residential buildings, and commercial shopping centers. Examples of these types of buildings are shown in Figures 1.5 to 1.11. Some of these advantages are:

- 1) Elimination of expensive formwork and scaffolding
- 2) Fast, economical construction cycle time — from initial grading to move-in
- 3) Lower insurance rates that are typical for non-combustible construction
- 4) Wide variety of exterior finishes such as colored concrete, exposed aggregate, graphic painting and form liner finishes
- 5) Easily modified structures for building expansion
- 6) Durable, long-life and low maintenance building

Perhaps the greatest advantage of tilt-up is the ease and speed of construction. Panels can be tilted with high capacity mobile cranes and braced in less than ten minutes. It is possible to construct the complete building shell, from foundation through the roof, for a 100,000 ft² warehouse with office space in 30 days or less.

1.5-Disadvantages

- 1) Certain architectural treatment may become costly because of the construction techniques
- 2) Lack of availability of qualified personnel and contractors
- 3) Weight of the panels on certain soils
- 4) Available space to cast panels
- 5) Temporary bracing during construction
- 6) Availability of lifting equipment
- 7) Structural integrity requires careful consideration





Fig. 1.3-Tilting front wall of

1987



Fig. 1.5-Apartment building

1.6-Scope of report

This report includes current basic design procedures relating to slenderness, panel loading, connections, roof diaphragms, lifting analysis, temporary bracing, construction planning, construction procedures at the jobsite, erection, and safety procedures, along with a discussion of concrete mixture proportions and methods and types of finishes. Because of the concern for energy conservation a section devoted to the construction of insulated sandwich wall panels is also included.

Following the recommendations contained in this report will reduce the need for experimenting at the jobsite. The five steps of design, planning, construction, erection, and creating finishes are crucial to a successful tilt-up project. With ample preplanning between the owner, contractor, concrete subcontractor, erection subcontractor, accessory suppliers, and architect/engineer, and close adherence to the ideas and suggestions in this report, tilt-up concrete construction can provide a quick, economical, and versatile method of constructing low and mid-rise buildings.



Fig. 1.6-Condominium

CHAPTER 2-DESIGN

2.1—General

2.1.1 Slenderness — Tilt-up buildings are typically low-rise structures of four stories or less in height, with the majority being one and two stories. Wall panels for these buildings are generally designed as load-bearing beam-columns spanning vertically between the ground floor and the roof, or intermediate floors. Typically, these panels support vertical gravity loads in combination with lateral loads such as wind, seismic, or earth pressures. Often the panels are very slender; slenderness ratios of



Fig. 1.7-Industrial building




Fig. 1.8-Service building



Fig. 1.9-Warehouse



Fig. 1.10-Office building