



## BSI Standards Publication

### Earthworks

---

Part 6: Land reclamation earthworks using dredged hydraulic fill

## National foreword

This British Standard is the UK implementation of [EN 16907-6:2018](#).

The UK participation in its preparation was entrusted to Technical Committee B/526/-/1, Earthworks.

A list of organizations represented on this committee can be obtained on request to its secretary.

This publication does not purport to include all the necessary provisions of a contract. Users are responsible for its correct application.

© The British Standards Institution 2018  
Published by BSI Standards Limited 2018

ISBN 978 0 580 91420 1

ICS 93.020

**Compliance with a British Standard cannot confer immunity from legal obligations.**

This British Standard was published under the authority of the Standards Policy and Strategy Committee on 31 December 2018.

### Amendments/corrigenda issued since publication

Date	Text affected
------	---------------

---

English Version

## Earthworks - Part 6: Land reclamation earthworks using dredged hydraulic fill

Terrassements - Partie 6 : Terre-plein  
en remblai hydraulique dragué

Erdarbeiten - Teil 6: Landgewinnung mit  
nassgebagertem Einbaumaterial

This European Standard was approved by CEN on 14 May 2018.

CEN members are bound to comply with the CEN/CENELEC Internal Regulations which stipulate the conditions for giving this European Standard the status of a national standard without any alteration. Up-to-date lists and bibliographical references concerning such national standards may be obtained on application to the CEN-CENELEC Management Centre or to any CEN member.

This European Standard exists in three official versions (English, French, German). A version in any other language made by translation under the responsibility of a CEN member into its own language and notified to the CEN-CENELEC Management Centre has the same status as the official versions.

CEN members are the national standards bodies of Austria, Belgium, Bulgaria, Croatia, Cyprus, Czech Republic, Denmark, Estonia, Finland, Former Yugoslav Republic of Macedonia, France, Germany, Greece, Hungary, Iceland, Ireland, Italy, Latvia, Lithuania, Luxembourg, Malta, Netherlands, Norway, Poland, Portugal, Romania, Serbia, Slovakia, Slovenia, Spain, Sweden, Switzerland, Turkey and United Kingdom.



EUROPEAN COMMITTEE FOR STANDARDIZATION  
COMITÉ EUROPÉEN DE NORMALISATION  
EUROPÄISCHES KOMITEE FÜR NORMUNG

CEN-CENELEC Management Centre: Avenue Marnix 17, B-1000 Brussels

## Contents

Page

<b>European foreword</b>	<b>v</b>
<b>Introduction</b>	<b>vi</b>
<b>1 Scope</b>	<b>7</b>
<b>2 Normative references</b>	<b>7</b>
<b>3 Terms and definitions</b>	<b>8</b>
<b>4 Symbols and abbreviations</b>	<b>11</b>
<b>5 Stages of land reclamation projects</b>	<b>12</b>
<b>6 Design aspects for earthworks with dredged hydraulic fill</b>	<b>12</b>
6.1 Introduction	12
6.2 Basis of Design	13
6.2.1 General	13
6.2.2 Scope of Work	13
6.2.3 The project site	13
6.2.4 Standards and Codes of Practice	14
6.2.5 Functional requirements	14
6.2.6 Boundary conditions and constraints	14
6.2.7 Performance requirements	14
6.2.8 Site data	15
6.2.9 Borrow area	15
6.2.10 Environmental constraints	15
6.2.11 Regulations, permits and licenses	15
6.3 General design aspects	15
6.3.1 Earth-structure design aspects	15
6.3.2 Morphological and environmental aspects	16
6.4 Boundary conditions affecting the execution	16
6.4.1 General	16
6.4.2 Locations of land reclamation area, borrow area and disposal site	17
6.4.3 Soil conditions at the land reclamation area	17
6.4.4 Soil conditions at the borrow area	17
6.4.5 Suitable fill material properties	17
6.4.6 Dredging close to existing structures	17
6.4.7 Construction tolerances	17
6.4.8 Return of process water	17
6.4.9 Ground improvement of the fill mass and the subsoil	18
6.4.10 Project execution time and milestones	18
6.5 Earthworks design considerations	18
6.5.1 Introduction	18
6.5.2 Land reclamation area	18
6.5.3 Borrow area	18
6.5.4 Available quantity of suitable fill material	19
6.6 Design considerations in relation to dredging equipment	20
<b>7 Technical specifications for earthworks with dredged hydraulic fill</b>	<b>20</b>
7.1 Introduction	20
7.2 Technical specifications for the subsoil	20
7.3 Technical specifications for the fill mass	20
7.4 Technical specifications for the fill material	21
<b>8 Data collection</b>	<b>21</b>
8.1 General	21
8.2 Bathymetrical and topographical data	22
8.3 Geotechnical and geophysical data	22
8.3.1 General	22

8.3.2	Geotechnical and geophysical data in the borrow area.....	22
8.3.3	Geotechnical and geophysical data in the land reclamation area.....	24
8.4	Hydrological and meteorological data.....	24
8.5	Seismic data.....	25
8.6	Morphological and environmental data.....	25
8.6.1	General.....	25
8.6.2	Sediment transport.....	25
8.6.3	Total Suspended Solids (TSS) and turbidity.....	25
8.6.4	Organic matter and gas.....	26
8.6.5	Contaminants.....	26
8.6.6	Underwater sound.....	26
8.7	Seabed features.....	26
8.8	Site constraints.....	27
<b>9</b>	<b>Equipment.....</b>	<b>27</b>
9.1	Selection of the dredging equipment.....	27
9.1.1	General.....	27
9.1.2	Selection of the dredging equipment based on the capabilities of the equipment.....	27
9.1.3	Selection of the dredging equipment based on hydraulic and meteorological conditions.....	28
9.1.4	Selection of the dredging equipment based on the presence of shipping.....	28
9.1.5	Selection of the dredging equipment based on environmental restrictions.....	28
9.2	Typical dredging equipment.....	28
9.3	Accuracy and tolerances.....	29
9.4	Minimal vessel requirements for monitoring and data logging.....	29
<b>10</b>	<b>Design of the execution of earthworks with dredged hydraulic fill.....</b>	<b>30</b>
10.1	Construction.....	30
10.1.1	General.....	30
10.1.2	Preparation phase.....	30
10.1.3	Construction phase.....	30
10.1.4	Post-construction phase.....	32
10.2	Selection of placement method.....	32
10.3	Preparation of the seabed for dredging and for the land reclamation works.....	33
10.4	Containment bunds.....	34
10.5	Process water management.....	35
10.6	Water table in the land reclamation area.....	35
10.7	Use of cohesive or fine grained materials.....	35
10.8	Ground improvement.....	36
<b>11</b>	<b>Quality control.....</b>	<b>36</b>
11.1	General.....	36
11.2	Quality Control Plan.....	36
11.3	Monitoring and testing.....	37
11.4	Dimensions and boundary conditions.....	37
11.4.1	Borrow area.....	37
11.4.2	Land reclamation area.....	38
11.5	Quality of the fill material.....	38
11.5.1	Source material in borrow area.....	38
11.5.2	Fill material in land reclamation area.....	38
11.6	Fill mass.....	38
11.6.1	Bearing capacity.....	38
11.6.2	Slope stability.....	39
11.6.3	Consolidation and deformations.....	39
11.6.4	<i>In situ</i> density and density index.....	39
11.6.5	Permeability.....	41
11.6.6	Frequency of testing.....	41
11.6.7	Environmental monitoring.....	42
11.7	Handover documentation.....	43

<b>Annex A (informative) Non EN and non ISO test and monitoring methods</b>	<b>44</b>
<b>Annex B (informative) Determination of minimum and maximum dry densities and density index</b>	<b>48</b>
<b>Bibliography</b>	<b>51</b>