

	DIN CEN/TR 14245	DIN
ICS 91.100.10	Supersedes DIN CEN/TR 14245 (DIN SPEC 18098):2015-01	
Cement – Guidelines for the application of EN 197-2: Assessment and verification of constancy of performance; English version CEN/TR 14245:2020, English translation of DIN CEN/TR 14245:2020-10		
Zement – Richtlinien für die Anwendung von EN 197-2: Bewertung und Überprüfung der Leistungsbeständigkeit; Englische Fassung CEN/TR 14245:2020, Englische Übersetzung von DIN CEN/TR 14245:2020-10		
Ciment – Lignes directrices pour l'application de l'EN 197-2: Evaluation et vérification de la constance de la performance; Version anglaise CEN/TR 14245:2020, Traduction anglaise de DIN CEN/TR 14245:2020-10		
Document comprises 42 pages		
Translation by DIN-Sprachendienst. In case of doubt, the German-language original shall be considered authoritative.		

A comma is used as the decimal marker.

National foreword

This document (CEN/TR 14245:2020) has been prepared by Technical Committee CEN/TC 51 “Cement and building limes” (Secretariat: NBN, Belgium).

The responsible German body involved in its preparation was *DIN-Normenausschuss Bauwesen* (DIN Standards Committee Building and Civil Engineering), Working Committee NA 005-07-13 AA “Cement (national mirror committee for CEN/TC 51 and ISO/TC 74)”.

Technical Reports are not part of the German body of standards.

Please tell us what you think of this Technical Report:

- preferably in a file with a table, e-mailed to nabau@din.de. The template for this table is available for download from www.din.de/stellungnahme;
- or send a hard copy to *DIN-Normenausschuss Bauwesen* (DIN Standards Committee Building and Civil Engineering), Saatwinkler Damm 42/43, 13627 Berlin.

Attention is drawn to the possibility that some of the elements of this document may be the subject of patent rights. DIN shall not be held responsible for identifying any or all such patent rights.

For current information on this document, please go to DIN’s website (www.din.de) and search for the document number in question.

Amendments

This standard differs from DIN CEN/TR 14245:2015-01 as follows:

- a) the guidelines in this document have been aligned with the changes made in EN 197-2;
- b) guidelines relating to AVCP for distributors and importers have been included in the document.

Previous editions

DIN-Fachbericht 197: 2001

DIN CEN/TR 14245 (DIN SPEC 18098): 2015-01

English Version

**Cement -
Guidelines for the application of EN 197-2:
Assessment and verification of constancy of performance**

Ciment -

Lignes directrices pour l'application de l'EN 197-2:
Evaluation et vérification de la constance de la performance

Zement -

Richtlinien für die Anwendung von EN 197-2:
Bewertung und Überprüfung der Leistungsbeständigkeit

This Technical Report was approved by CEN on 8 December 2019. It has been drawn up by the Technical Committee CEN/TC 51.

CEN members are the national standards bodies of Austria, Belgium, Bulgaria, Croatia, Cyprus, Czech Republic, Denmark, Estonia, Finland, France, Germany, Greece, Hungary, Iceland, Ireland, Italy, Latvia, Lithuania, Luxembourg, Malta, Netherlands, Norway, Poland, Portugal, Republic of North Macedonia, Romania, Serbia, Slovakia, Slovenia, Spain, Sweden, Switzerland, Turkey and United Kingdom.



EUROPEAN COMMITTEE FOR STANDARDIZATION
COMITÉ EUROPÉEN DE NORMALISATION
EUROPÄISCHES KOMITEE FÜR NORMUNG

CEN-CENELEC Management Centre: Rue de la Science 23, B-1040 Brussels

Contents

Page

European foreword.....	4
Introduction to this Guidelines Document.....	5
1 Scope	6
2 Normative references.....	6
3 Terms and definitions	7
4 Factory production control	10
4.1 General requirements	10
4.1.1 Concept	10
4.1.2 Works' quality documentation.....	10
4.1.3 Quality management system.....	11
4.1.4 System of documentation.....	13
4.2 Internal quality control.....	14
4.2.1 Process control.....	14
4.2.2 Measuring and testing	16
4.2.3 Handling, storage, packaging and delivery.....	17
4.3 Autocontrol testing of samples	17
4.3.1 Sampling and testing.....	17
4.3.2 Corrective action	19
4.3.3 Measuring and test equipment for autocontrol testing	21
4.3.4 Quality records.....	21
5 Tasks for the purpose of certification	21
5.1 Assessment of the performance of the cement.....	21
5.2 Initial inspection of the manufacturing plant and of factory production control	22
5.2.1 Inspection of a new factory.....	22
5.2.2 Inspection of an existing factory.....	22
5.2.3 Criteria for the assessment of the production equipment	23
5.2.4 Criteria for the assessment of laboratories	23
5.3 Continuing surveillance, assessment and evaluation of factory production control	23
5.3.1 Inspection of the factory and the factory production control.....	23
5.3.2 Evaluation of the results of autocontrol testing of samples	25
5.4 Audit-testing of samples taken at the factory/depot	29
5.4.1 Sampling.....	29
5.4.2 Testing.....	30
5.4.3 Evaluation of test results	31
5.5 Reports.....	31
5.6 Actions to be taken in the event of non-conformity	32
5.6.1 Following inspection of the factory production control and evaluation of the results of autocontrol testing	32
5.6.2 Following evaluation of the results of the audit-testing	33
6 Procedure for certification of constancy of performance of the product.....	33
Annex A (normative) Evaluation of the representativeness and the accuracy of the 28 day strength test results	36
A.1 General.....	36
A.2 Sets of results considered	36

A.3	Evaluation procedure.....	36
A.3.1	Introduction.....	36
A.3.2	Symbols	36
A.3.3	Evaluation of whether set A and set B belong to the same population (sampling error check).....	37
A.3.4	Comparison between set B and set C in order to check the accuracy of the autocontrol testing (testing error check)	38
A.3.5	Masonry cement.....	38
A.3.6	Calcium aluminate cement.....	38
Annex B (informative)	Procedure for certification of constancy of performance of cement.....	39
Bibliography		40